

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2020-21 Dated: 29-01-2021

APPROVED TENDER SCHEDULE -'B'

Item 08

Name of Work :-Improvements to Roads and Drains at Sai Nagara 2 and Surrounding area in Ward No 03

SI	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri R SHIVARAM	
				Rate	Rate in Words
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. As Per the Direction of Engineer In charge of the work.	Cum	860.10	230.65	Two Hundred Thirty Paise SixtyFive Only
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. As Per the Direction of Engineer In charge of the work.	Cum	129.02	5765.51	Five Thousand Seven Hundred SixtyFive Paise FiftyOne Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH	Cum	281.67	7523.73	Seven Thousand Five Hundred TwentyThree Paise SeventyThree Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಯಲಹಂಕ ವಿಭಾಗ

	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. As Per the Direction of Engineer In charge of the work.	Tonne	18.46	68071.58	SixtyEight Thousand SeventyOne Paise FiftyEight Only
5	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including form work, lift charges, curing and concrete finished surface on both sides etc, and complete as per the directions of Engineer in charges. (Data Rate). As Per the Direction of Engineer In charge of the work.	Sqm	692.10	2445.67	Two Thousand Four Hundred FortyFive Paise SixtySeven Only
6	Providing and fixing Precast RCC slab of 250mm thick for Culverts made of Plain/Reinforced Cement Concrete design mix M25 with OPC@340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates@0.47cum, with superplasticizer@3lts confirming to 189103-1999 Reaffirmed-2008, Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications and pointing for joints 1:3 cement mortar including form work, lift charges, curing and concrete finished surfaces on both sides etc, (Data Rate). complete and as per the directions of Engineer in-Charge.	Sqm	10.65	5669.94	Five Thousand Six Hundred SixtyNine Paise NinetyFour Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.